

# Temporary wood structure for Theater St. Gallen

St. Gallen, CH



## Project details

Client	Kanton SG, Baudepartement
Architecture	Gähler Flühler Architekten
Project type	Art and culture
Construction type	Wood element construction
Services	JC
Construction	2020
Locality	St. Gallen
Country	Switzerland

## The temporary theatre houses two seasons of arts and culture

In the park beside the Tonhalle concert hall in St. Gallen, a temporary theatre for 500 spectators was created. A temporary stage was required due to the refurbishment of the outdated theatre. The stage will host the performances of the St. Gallen city theatre for two seasons. Blumer Lehmann realised the timber construction as full-service general contractor. Named 'UM!BAU', the temporary structure is 50 m long and 26 m wide. The spruce and fir elements were prefabricated at our plant. A total of 350 m<sup>3</sup> of wood was used. The roof and facades are clad with section sheet.

The temporary theatre construction was ready for occupation by mid-September 2020, and includes a stage, orchestra pit, foyer, gallery, storage area and recreation room for artists. The timber construction work took a total of 14 weeks from mid-April until the end of July 2020. A timber substructure installed right on top of the roof of the existing underground car park serves as the foundations of the prefabricated timber structure, which was constructed on top of this. Wet rooms were installed in containers and the stands are also of a timber construction. The plan is not to dispose of the temporary structure once it is no longer in use but to reconstruct it elsewhere. We have plenty of ideas but have yet to find the right location.

## Specific Contact



### Migga Hug

Head of GC & TC Services |  
Architectural planning | Switzerland  
Member of the Division Management

T +41 71 388 58 23  
[migga.hug@blumer-lehmann.com](mailto:migga.hug@blumer-lehmann.com)

# Temporary wood structure for Theater St. Gallen

St. Gallen, CH



Foyer with bar in the 'UM!BAU' temporary theatre at the St. Gallen city theatre.



The temporary theatre construction is complete with a stage, orchestra pit, foyer, gallery, storage area and recreation room for artists.



Das Theaterprovisorium fügt sich durch seine Form und Bauweise harmonisch in die Umgebung des Brühlparks ein.

Der hauptsächliche Werkstoff Fichten- und Tannenholz – sichtbar und roh verbaut – setzt Akzente.

# Temporary wood structure for Theater St. Gallen

St. Gallen, CH



Für den Theaterbetrieb wie für das Publikum vorteilhaft: Die Ersatz-Spielstätte in Holzbauweise befindet sich unmittelbar neben dem Stammhaus des Theater St. Gallen.



Neben Fichten- und Tannenholz wurden für den Brand- und Schallschutz weitere Holzwerkstoffe verbaut.



Die Fassaden und das Dach sind mit Trapezblech abgedeckt.